

GENERAL

FOUNDATIONS

2 BACK FILL OVER CONCRETE FOUNDATIONS TO BE
COMPACTED TO 95% MOD AASHTO IN LAYERS NOT
EXCEEDING 150mm TO FORMATION LEVEL OF THE
SURFACE BED.

ALL REINFORCEMENT IN FOUNDATIONS TO HAVE MINIMUM CONCRETE COVER OF 40mm.

CONCRETE WORK

2.2 MINIMUM CONCRETE CUBE STRENGTH

3 MINIMUM CONCRETE COVER TO REINFORCEMENT:
25mm ABOVE GROUND
40mm BELOW GROUND

BRICKWORK CONSTRUCTION

2 BRICK WALLS LAYOUT AND DIMENSIONS TO ARCHITECT'S LATEST DRAWINGS.

ENT

CONSULTANTS

IDENTITY SURVEY OF



STRUCTURAL ENGINEERS

/STRUCTURAL ENGINEERS

SUBJECT

WORKING TITLE

SIGNED	VJ	APPROVAL BY CLIENT
--------	----	--------------------

D2518 SS 04

SECTION B-B
SCALE 1:25

